

The Philips logo is displayed in a white rounded rectangle on a dark blue background. The word "PHILIPS" is written in a bold, blue, sans-serif font.

Case study

Tunnel Lighting

Case Study

Lighting the way for ground-breaking tunnel refurbishment

Location: A55, Wales

Philips Lighting: Philips FlowStar, Philips T-line LED



Fast Facts

Customer
SPIE

Location
A55, Wales: Conwy, Pen Y Clip and Penmaenbach tunnels

Philips Products
Philips FlowStar, Philips T-line LED



required new stainless steel primary fixing grid and cable trays. It also had to provide high lighting levels and uniformity in the threshold and transition zones and provide enhanced safety levels via dual redundant controls and adherence to rigorous fire safety requirements.

The A55 Penmaenbach Tunnel in particular, also required the existing lighting to be retained until the new lighting was installed and commissioned. This was because the tunnel needed to be opened to live traffic each morning after night-time refurbishment work.

“The projects were delivered to demanding schedules with short delivery and installation/commissioning times, so Philips’ ability to provide one-stop-shop delivery and commissioning was critical,” Steve Henry continued.

The right lighting

A co-ordinated design approach was essential to account for tunnel curvatures and to avoid clashes with other essential services such as the large ventilation fans.

The lighting calculations ensure that luminaire photometric performance is fully optimised and in close correlation to BS5489-2:2008 luminance reduction curves. The design for the Conwy Eastbound and Pen Y Clip tunnels adopts a linear approach with luminaires arranged about the centreline of the carriageway. In the Penmaenbach tunnel the new lighting is

side-mounted to avoid the existing centreline lighting.

All of the designs achieve exceptionally high longitudinal lighting uniformity and levels of light across the full width of the carriageway, with the client setting tough challenges to provide these even well above the minimum requirements of BS 5489-2.

Each design is primarily based on a uni-directional traffic arrangement with supplementary lighting to allow for a reduced speed contra-flow arrangement at the normal exit portal, also used in-part to derive the normal exit lighting. The interior tunnel lighting is provided by Philips T-line LED luminaires spaced to provide constant longitudinal lighting. These are controlled via two fixed dimming stages between night and day driving conditions.

A major advantage of the linear lighting design is that of driver comfort; given that there is little or no sensation of flicker, which can often be sensed when driving below widely spaced and very bright luminaires. The linear lighting also acts as desirable subliminal driver guidance through the length of the long tunnel.

Boost lighting is provided using Philips FlowStar luminaires mounted in a single row, marginally offset from the interior luminaire row. The boost lighting is fully dynamic during daylight hours, continually adapting to changes in exterior ambient light conditions, to ensure drivers have good vision into the tunnel from the approach road, across all weather and seasonal conditions.

A ground-breaking road tunnel refurbishment project is using Philips LED tunnel lighting technology and controls to meet demanding performance criteria.

Following its recent M&E upgrade by contractors SPIE, the Conwy Eastbound tunnel on the A55 became the UK’s first long (c.1km) high-speed road tunnel to be lit with an all-LED continuously dimming system. This follows a lighting upgrade project in the Westbound bore in 2013, which was illuminated by a hybrid LED-dimmed/HPS-switched scheme.

The Conwy tunnel is one of three high speed tunnels on the A55 where SPIE has recently installed Philips tunnel lighting in their refurbishment, the others being the 1km Pen Y Clip tunnel and the 0.65km tunnel at Penmaenbach. The projects were carried out under the Welsh Government’s Ancillary Framework Agreement and on average delivered 60% energy savings, 95% maintenance cost savings and 40% installation cost savings.

“All three of these projects imposed demanding specifications on the lighting, as well as presenting budgetary and scheduling

challenges,” recalled SPIE’s Steve Henry, Operations Manager. “We selected the Philips luminaires and controls as they clearly met the performance criteria at the lowest installation cost, and were backed by the company’s extensive experience of delivering major tunnel lighting contracts,” he added.

Project criteria

The principles applied to the tunnel upgrades are exemplified by the system selected for the Conwy Eastbound tunnel. The previous lighting scheme in the Conwy tunnel – using fluorescent interior zone lighting with high pressure sodium boost lighting – was no longer compliant with the latest British Standards and the equipment was at the end of its design life.

This presented the perfect opportunity to exploit the cost savings and environmental benefits of LED lighting, while also ensuring best value for the client over a 20 year design lifetime. In addition, the chosen lighting needed to offer a fast and reliable installation method with full galvanic isolation (anti corrosion) and plug and socket connections, that would also minimise the cost of the





External photometers continually monitor these daylight levels and feed brightness data to the lighting controls, which instantaneously determine the correct corresponding lighting required within the tunnel.

The FlowStar Boost luminaires are very powerful (50klm at full 435W power) so just a single end-to-end lighting row can achieve up to the 10,000 lux needed to balance mid-summer sunshine on the approach road.

Reduced installation time

The project also took advantage of the proven clamping system on Philips road tunnel luminaires. Each luminaire has a mounting flange running the full length of two sides as part of the extrusion/structure. Purpose-designed mounting clamps engage the luminaire flanges with the principal support structure to form a quick and reliable fixing with similar quick de-mounting potential should this ever be needed under future maintenance.

This simple style of mounting is very flexible, given the wide luminaire mounting flanges, and does not rely on accurate primary fixing locations to be arranged; thereby reducing installation time and material costs.

Lighting control

The project also features a complete tunnel lighting control system using two Philips B-ScoutMaster control panels arranged in a duty/standby configuration for enhanced resilience. These are linked to Philips L20 photometers mounted on columns at the stopping distance from the entrance portals. The duty lighting control panel

instructs local control units (each serving up to 10 LED drivers) to switch to 'on', 'dim' or 'off' to create the required lighting pattern at any given time.

The controls are designed to operate as a fully stand-alone system under normal conditions, with the ability to link to the SCADA (Supervisory Control and Data Acquisition) control system to provide high level monitoring for the tunnel operating staff and essential override control and data reporting.

Flawless Execution

As well as carrying out preliminary site measurements and surveys, the Philips team provided a functional design specification and worked closely with SPIE in optimising the design for ease and speed of installation – as well as commissioning on site. Factory acceptance testing demonstrated equipment suitability prior to installation. Philips also carried out the commissioning and relevant Site Acceptance Testing.

"In all of the recent extensive tunnel refurbishment projects good communications and teamwork has been essential in meeting the client's expectations; on time delivery and to budget, with minimum disruption to motorists. The collaborative approach of the Philips Tunnels Lighting Team and their specialist expertise, has proved invaluable to the success of all the A55 projects," Steve Henry concluded.

If you would like to see more lighting projects or have an enquiry, please visit us at;

www.philips.co.uk/lighting or email: lighting.uk@philips.com



©2016 Koninklijke Philips Electronics N.V.
All rights reserved. Reproduction in whole or in part is prohibited without the prior written consent of the copyright owner. The information presented in this document does not form part of any quotation or contract, is believed to be accurate and reliable and may be changed without notice. No liability will be accepted by the publisher for any consequence of its use. Publication thereof does not convey nor imply any license under patent- or other industrial or intellectual property rights. Date of release: April 2015

Contact details:

Guildford
Philips Lighting, Philips Centre, Guildford Business
Park, Guildford, GU2 8XH
Tel: 0845 601 1283

Dublin
Philips Electronics Ireland Ltd, Philips House, South
County Business Park, Leopardstown, Dublin 18
Tel: +353 1 764 0000

Email: lighting.uk@philips.com
www.philips.co.uk/lighting